



Request for Pricing

## **Boissevain Health Centre AHU Replacement**

**Project SO 6169**

### **Boissevain Health Centre AHU-3**

**Replacement of existing Trane AHU-3. Work to include:**

- Removal and replacement of existing AHU
- To include all costs associated
- Crane/truck
- Any sod, grounds, asphalt repair
- All required permits
- Curbing required
- Roof repairs for removal or installation
- Startup and training
- Controls integration and/or trouble shooting
- New BACnet points and required wiring
- All required wiring/electrical
- Hinged door access
- Merv 8 filters
- Comparative Enthalpy Economizer
- Low Leak Outside Air Damper
- Single Speed Fan only required
- Unit must be able to be controlled and monitored fully by existing facility controls
- Required maintenance areas to be easily accessible
- METASYS DDC field controllers, panels, sensors, actuators, etc. for control and monitoring including all required wiring
- All requirements for unit to be added to current MATASYS system for control and monitoring

**Disclaimer: all items above are not all encompassing. It is up to the contractor to confirm existing and requirements.**

**Mandatory contractor site review 0930 May 01, 2025.**

**Tender closing:** 2:00 p.m. local time on Thursday May 15<sup>th</sup>, 2025. Pricing to be valid for 60 days from submission.

**Enquiries and tender submittals to be submitted to:**

Chris Couling. Area Manager

Email: [ccouling@pmh-mb.ca](mailto:ccouling@pmh-mb.ca)

204-483-6153